Delta Flooring, Inc.

Bid Proposal

Post Office Box 47 Bay Minette, AL 36507 Phone: (251) 937-0506 Fax: (251) 937-0560

213 East 1st Street

August 20, 2024

Subject: Baldwin County Sheriff's Office - Robertsdale

Reference: Flooring - 1st Floor Only

Delta Flooring, Inc. is pleased to submit for your approval our proposal to furnish and install the following flooring for the above subject facility. Our pricing and scope of work is as follows:

Amount \$35,109.00

- Skim Coat Existing Ceramic Floor Tile in Corridors and Offices to Receive New LVT.
- Demo Existing Carpet in all Offices to Receive New LVT.
- Demo Existing Rubber Cove Base.
- Provide and Install New LVT Over Existing Ceramic Tile and Offices, and Stairwell Landings. (Material Allowance \$2.00 Sq. Ft.)
- Demo Existing Stairway Treads and Risers.
- Provide and Install New Rubber Stairway Treads and Risers.
- Provide and Install 4.5" Rubber Cove Base.
- No Work in Men's/Women's Restrooms.
- No Work in Rm #112 (Lab).
- No Work in Rm #121 (Radio Room)
- Minor Floor Prep. Any Leveling Required to Bring Substrate with in Tolerance is Excluded.
- Movement of Furniture Excluded
- All Computers/Electronics Must be Removed Prior to Installation.

Notations and Clarifications:

- 1. Normal services will need to be provided such as electricity, lighting, ventilation, air, trash receptacles, water, etc.
- 2. Payment terms: Progressive payments Net 30 days from date of invoice.
- 3. The schedule of work must allow open access to the areas that are to be covered;
- Work will be performed working hours Monday thru Friday 7AM to 3:30PM.
- 5. Proposal is valid for 30 days.

Thank you for giving Delta Flooring the opportunity to submit our proposal. If you should have any questions or require additional information, please give me a call.

Delta Flooring, Inc. Regards.

Russell Schmitz

Pfeffer Floor Covering, Inc.

QUOTE: 16701 DATE: 7/24/2024

P.O. Box 503 703 D' Olive Street Bay Minette, AL 36507 (251)937-2189

> Baldwin County Sheriff's Office CID Robertsdale, AL

SALESPERSON	JOB	PAYMENT TERMS	DUE DATE
Arlene Pfeffer			

	DESCRIPTION	UNIT PRICE	LINE TOTAL
Vinyl Plank	Timber Grove II 20 mil - Pergola - & adhesive		\$18,541.00
Floor prep	Removal of existing carpet and prep over existing ceramic or removal if needed		\$3,900.00
Installation	Install glue down vinyl plank		\$10,400.00
Molding	Material & labor for cove base or qtr round As needed		\$4,935.00
Stairs	Remove existing and install new stair treads and landings		\$5,200.00
		DEPOSIT	
	TOTAL	\$42,976,00	