

CHANGE ORDER

Order No. 1

Date: May 5, 2023

Agreement Date: November 11, 2022

NAME OF PROJECT: **Drainage Improvement Projects (HW21154000 Leiterman Rd,
HW21156000 Shoots Ln, HW21151000 CR-87)**

OWNER: Baldwin County Commission

CONTRACTOR: McElhenney Construction Company, LLC


The following changes are hereby made to the CONTRACT DOCUMENTS:

Changes for HW21154000 Leiterman Road

Increase Construction Time by 10 working days	No Charge
Credit for deletion of Pay Item 630A-001 Steel Beam Guardrail, Class A, Type 2	-\$ 7,430.40
Addition of Pay Item 630A-001* Steel Beam Guardrail, Class A, Type 2 (8' posts)	\$ 8,456.40
Addition of Pay Item 524A-011* Culvert Concrete (Cast In Place) (Parapet and Wingwall Extension)	\$33,000.03
TOTAL	\$34,026.03

The Original (CONTRACT PRICE)	\$1,748,268.72
Net change by previously authorized Change Orders	\$ 0.00
The (Contract Price) prior to this Change Order was	\$1,748,268.72
The new (Contract Price) will be (increased) by this Change Order	\$ 34,026.03
The new (CONTRACT PRICE) including this CHANGE ORDER will be	\$1,782,294.75

The Original (CONTRACT TIME)	185 working days
The (CONTRACT TIME) prior to this Change Order was	185 working days
The (CONTRACT TIME) will be (increased) by this Change Order	10 working days
The new (CONTRACT TIME) including this CHANGE ORDER will be	195 working days

CONTRACTOR:  5/8/23

RECOMMENDED:   5-8-2023

OWNER: _____



Tyler Mitchell, PE
Construction Manager
Baldwin County Highway Department
22070 Hwy 59
3rd Floor
Robertsdale, AL 36567

Your Reference
BCP-21154000

Our Reference
502100456

107 Saint Francis St
Suite 2900
Mobile AL 36602
United States of America

T +1 (251) 343 4366
F +1 (251) 343 6902
mottmac.com

BCHD FEMA Repair Sites, Leiterman Road, Proposal to Address Existing Slope Conditions

May 5, 2023

Dear Tyler,

Attached please find McElhenney Construction Company's (MCC) proposal to address the box culvert slope condition on the Leiterman Road project. While not explicit in their proposal, based on discussions held with MCC the work proposed includes extending the height of all culvert parapets, and wingwalls by 2' to flatten the slope so that it may then be covered with filter fabric and Class II rip rap. Also, the planned 6' guardrail posts will be replaced with 8' long posts considering the steepened slope conditions. We recommend the County accept MCC's proposal.

Should you have any questions, please do not hesitate to call.

Sincerely,

William H Klepac

Digitally signed by William H Klepac
DN: cn=William H Klepac,
c=US, email=AD141020000180ABE3A5E0000B622F,
ou=Alabama, cn=US
Date: 2023.05.05 16:01:42 -0500

William H. Klepac, PE
Principal Project Manager
T 251-406-8281
bill.klepac@mottmac.com



May 5, 2023

Mr. Jacob Henry
Mott MacDonald
107 St. Francis Street
Mobile, AL 36602

RE: BCP – 21154000 - Leiterman Road - Baldwin County

Mr. Henry,

McElhenney Construction Company proposes the following for the repair of the slopes on Leiterman Road using the existing contract items:

ITEM NO.	ITEM DESCRIPTION	EST QTY	UNIT	UNIT PRICE	QTY	AMOUNT
524A011	Culvert Concrete (Cast in Place)	9	CY	\$3,666.67	9	\$33,000.00

Furthermore, the guardrail on this project will need to be 8' post. Below is the price for this adjustment:

ITEM NO.	ITEM DESCRIPTION	EST QTY	UNIT	UNIT PRICE	QTY	AMOUNT
630A001	Steel Beam Guardrail, Class A, Type 2 8' Post	180	LF	\$ 46.98	180	\$ 8,456.40
630A001	Steel Beam Guardrail, Class A, Type 2	180	LF	\$ - 41.28	180	(\$7,430.40)

If this work is approved, we would like to request 10 additional working days. If you have any questions, please let me know.

Sincerely,

A handwritten signature in black ink, appearing to read 'Robert McDonough', written in a cursive style.

Robert McDonough
Project Manager