

HARRIS & CO.

Land and Fence

Harris and Company, LLC.
Robertsdale, Alabama

DATE: 5-7-2022

CUSTOMER: Baldwin County

Removal and disposal of decking boards, frame boards, hand rails
and 1x4 deco. "Everything decked up."

Replace frame boards with 2x6 treated

Replace Deco 1x4 with 1x4 treated

Use 3-3.5 inch exterior decking screws

Add 3 joist 2x6's treated per bay (to meet specs for composite board)

Replace deck boards with composite decking (5/4x6)

Replace top rail with double composite decking

Use all stainless screws for composite decking

total Estimate = \$26,800.00

Approx 220 pieces of Evergrain Decking

Approx 150 treated 2x6's

Approx 120 treated 1x4's

Approx 100 2x6 joist hangers

All screws are exterior and stainless

HARRIS & CO.

DATE

CUSTOMER

DATE