

Baldwin County Highway Department Estimate Sheet

DATE	1/30/2019	Area: 200 / Paul Penry			
REQUESTED BY:	Frank Lundy	SPONSORED BY:		LENGTH	WIDTH
LOCATION	Flowers Road/ From US Hwy 90 north approx. 630'			630 FT	18 FT
Scope of Work:	Material cost to widen road from 12ft to 18ft to accommodate 2 way traffic and improve drainage along roadway				
ITEM	DESCRIPTION	UNITS	QUANTITY	UNIT COST	SUBTOTAL
	MATERIAL				
	LIMESTONE BASE (DELIVERED)	TONS	106	\$ 22.85	\$ 2,422.10
	SAND/CLAY BASE	YARDS	100	\$ 1.75	\$ 175.00
	PIPE RCP 29" x 18" (Includes sloped end sec)	FEET	16	\$ 27.00	\$ 432.00
	GRASS SEED	LBS	20	\$ 1.72	\$ 34.40
	SOD (DELIVERED) CENTIPEDE 30" ROLLS	SQ YDS	250	\$ 1.55	\$ 387.50
	ASPHALT	TONS	160	\$ 56.65	\$ 9,064.00
	TOTAL			\$ -	\$ 12,515.00