

**BALDWIN COUNTY**

HIGHWAY DEPARTMENT

P.O. Box 220

SILVERHILL, ALABAMA 36576

TELEPHONE: (251) 937-0371

FAX (251) 937-0201

JOEY NUNNALLY, P.E.
COUNTY ENGINEER**SCOPE OF WORK**

October 1, 2020

BALDWIN COUNTY PROJECT
 INSTALLATION OF HELPER BENTS
 PINE GROVE ROAD EXTENSION OVER STYX RIVER

SUMMARY OF QUANTITIES

PAY ITEM	NEEDED TOTALS	COUNTY SUPPLIED	CONTRACTOR SUPPLIED
Base Bid			
10" H-pile	260 LF	200 LF	60 LF
I Beam Cap 17" X 12"	68 LF	68 LF	
Alternate at Bent 2			
10" H-pile	260 LF		260 LF
S18 X 54.7 Cap	68 LF		68 LF

PROJECT NOTES:

1. The County will provide varying length pile totaling approximately 200 LF. Contractor shall provide additional pile of matching dimensions to meet required quantities. A Vibro-Hammer shall be used to install piles to required bearing. Welded connections for splices shall be used. All work shall be done with approved methods, material and experienced personnel.
2. The County will provide (2) pile caps approximately 34 LF per cap.
3. The County will remove the existing guardrail, posts, and spacer blocks and replace when necessary.
4. For this specific operation traffic control will be provided by Baldwin County and the bridge will be closed.
5. The structure is weight-restricted, but the County will consider approving an engineered plan to place a crane, cherry-picker etc. on the deck to facilitate ease in construction.
6. The following price shall include all labor, materials, equipment, overhead, profit, insurance, etc., to cover the finished work of the kinds called for.
7. Work shall include construction of the helper bents as detailed in the attached drawing at Abutments 1 and 3. Bent 2 to be included at discretion of the County.
8. All welding and cutting, bolts, shims, plates, labor and any other items needed to complete the repair shall be a subsidiary obligation of the pile cap installation.

9. Cutting piles shall be a subsidiary obligation of piling driven.
10. All materials must conform to ALDOT Standard Specifications for Highway Construction, 2018 Edition.
11. Painting or coating will not be required.
12. The Bidder must understand that the County may reduce line-item quantities so as not to overrun the budget for this project.
13. Pile shall be driven according to ALDOT SPECS.
14. If it is required that the contractor must supply the piling, it must be inspected and approved first by the County before being used for construction.
15. Additional helper bents at Bent 2 will be an alternate for this project. All materials and labor will be furnished by the contractor for Bent 2. All materials provided can be previously used but will be inspected by Baldwin County before acceptance for use for this project.
16. Contractor shall locate and protect all utilities within the work area prior to starting work. It will be the contractor's responsibility at his expense to repair any utilities damaged by his work.

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	Pilings Furnished By County and Driven By Contractor	200	LF	150.00	30,000.00
2	Pilings Furnished By Contractor and Driven By Contractor	60	LF	174.00	10,440.00
3	Caps Furnished By County and Installed By Contractor	68	LF	95.00	6,460.00
4	Cost For Splicing Piles	10	EACH	300.00	3,000.00
TOTAL BASE BID					49,900.00

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
A1	Bent 2 (Alternate) Piling Furnished and Driven By Contractor	260	LF	185.00	48,100.00
A2	Bent 2 (Alternate) Cap Furnished and Installed By Contractor	68	LF	200.00	13,600.00
TOTAL ALTERNATE BID					61,700.00

NUMBER OF **WORKING DAYS** FOR COMPLETION OF BASE BID 5 WORKING DAYS.
AN ADDITIONAL NUMBER OF 2 WORKING DAYS WILL BE PROVIDED IF COUNTY
ELECTS TO GO WITH THE BENT 2 ALTERNATE.

ALL QUOTES MUST BE TURNED IN TO THE BALDWIN COUNTY HIGHWAY
DEPARTMENT AT 22070 HIGHWAY 59 ROBERTSDALE, AL 36567. **ATT: JEREMY
HOWELL** BY 11:00am ON OCTOBER 9th 2020.

ANY BIDS RECEIVED AFTER 11:00 AM WILL NOT BE CONSIDERED.

CONTRACTOR SHALL BEGIN WORK NO LATER THAN 15 DAYS AFTER RECEIVING
THE NOTICE TO PROCEED.

Company Name:

Newell & Bush, Inc.

Signature:

[Signature]



BALDWIN COUNTY

HIGHWAY DEPARTMENT

P.O. Box 220

SILVERHILL, ALABAMA 36576

TELEPHONE: (251) 937-0371

FAX (251) 937-0201

JOEY NUNNALLY, P.E.
COUNTY ENGINEER

SCOPE OF WORK

October 1, 2020

BALDWIN COUNTY PROJECT
INSTALLATION OF HELPER BENTS
PINE GROVE ROAD EXTENSION OVER STYX RIVER

SUMMARY OF QUANTITIES

PAY ITEM	NEEDED TOTALS	COUNTY SUPPLIED	CONTRACTOR SUPPLIED
Base Bid			
10" H-pile	260 LF	200 LF	60 LF
I Beam Cap 17" X 12"	68 LF	68 LF	
Alternate at Bent 2			
10" H-pile	260 LF		260 LF
S18 X 54.7 Cap	68 LF		68 LF

PROJECT NOTES:

1. The County will provide varying length pile totaling approximately 200 LF. Contractor shall provide additional pile of matching dimensions to meet required quantities. A Vibro-Hammer shall be used to install piles to required bearing. Welded connections for splices shall be used. All work shall be done with approved methods, material and experienced personnel.
2. The County will provide (2) pile caps approximately 34 LF per cap.
3. The County will remove the existing guardrail, posts, and spacer blocks and replace when necessary.
4. For this specific operation traffic control will be provided by Baldwin County and the bridge will be closed.
5. The structure is weight-restricted, but the County will consider approving an engineered plan to place a crane, cherry-picker etc. on the deck to facilitate ease in construction.
6. The following price shall include all labor, materials, equipment, overhead, profit, insurance, etc., to cover the finished work of the kinds called for.
7. Work shall include construction of the helper bents as detailed in the attached drawing at Abutments 1 and 3. Bent 2 to be included at discretion of the County.
8. All welding and cutting, bolts, shims, plates, labor and any other items needed to complete the repair shall be a subsidiary obligation of the pile cap installation.

9. Cutting piles shall be a subsidiary obligation of piling driven.
10. All materials must conform to ALDOT Standard Specifications for Highway Construction, 2018 Edition.
11. Painting or coating will not be required.
12. The Bidder must understand that the County may reduce line-item quantities so as not to overrun the budget for this project.
13. Pile shall be driven according to ALDOT SPECS.
14. If it is required that the contractor must supply the piling, it must be inspected and approved first by the County before being used for construction.
15. Additional helper bents at Bent 2 will be an alternate for this project. All materials and labor will be furnished by the contractor for Bent 2. All materials provided can be previously used but will be inspected by Baldwin County before acceptance for use for this project.
16. Contractor shall locate and protect all utilities within the work area prior to starting work. It will be the contractor's responsibility at his expense to repair any utilities damaged by his work.

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	Pilings Furnished By County and Driven By Contractor	200	LF	38 ⁰⁰	7,400 ⁰⁰
2	Pilings Furnished By Contractor and Driven By Contractor	60	LF	107 ⁰⁰	6,420 ⁰⁰
3	Caps Furnished By County and Installed By Contractor	68	LF	1,010 ⁰⁰	68,680 ⁰⁰
4	Cost For Splicing Piles	10	EACH	500 ⁰⁰	5,000 ⁰⁰
TOTAL BASE BID					\$87,700 ⁰⁰

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
A1	Bent 2 (Alternate) Piling Furnished and Driven By Contractor	260	LF	44 ⁰⁰	11,440 ⁰⁰
A2	Bent 2 (Alternate) Cap Furnished and Installed By Contractor	68	LF	180 ⁰⁰	12,240 ⁰⁰
TOTAL ALTERNATE BID					\$23,680 ⁰⁰

NUMBER OF **WORKING DAYS** FOR COMPLETION OF BASE BID 5 WORKING DAYS.
 AN ADDITIONAL NUMBER OF 2 WORKING DAYS WILL BE PROVIDED IF COUNTY
 ELECTS TO GO WITH THE BENT 2 ALTERNATE.

ALL QUOTES MUST BE TURNED IN TO THE BALDWIN COUNTY HIGHWAY
 DEPARTMENT AT 22070 HIGHWAY 59 ROBERTSDALE, AL 36567. **ATT: JEREMY
 HOWELL** BY 11:00am ON OCTOBER 9th 2020.

ANY BIDS RECEIVED AFTER 11:00 AM WILL NOT BE CONSIDERED.

CONTRACTOR SHALL BEGIN WORK NO LATER THAN 15 DAYS AFTER RECEIVING
 THE NOTICE TO PROCEED.

Company Name:

MCTHUS CONSTRUCTION, LLC

Signature:

[Signature]