



Phone (251) 943-1112

220 W. Laurel Ave, P.O. Box 669  
Foley, AL 36536

Fax (251) 943-1109

## PROPOSAL

January 19, 2021

Baldwin County Building Maintenance  
Attn. Christel Watson

Re: East Fork Landfill Scale House

Per our onsite inspection and attached drawings we propose to install deck structures at the scale house office per the following scopes of work:

- 5'x48' covered deck on North side with tie-in steps to scale surface
- 5'x25' ramp with 5'x5' landing on West side
- Two 5'x5' covered deck landings with steps on South side
- Deck surface to be composite 5/4" thick Veranda 15 yr
- Sub structure to be 2x6 joists at 24" o.c. supported by continuous 2x8 girders attached to 4x4 posts embedded a minimum 3' into ground and encased with concrete collar
- Covered awnings over deck areas to be 29 gauge galvalume Tuff Rib panels on treated 2x4 wood purlins
- All lumber to be standard treated pine

Cost for all above: **\$19,200.00**

Prices include cleanup and haul off of all debris and trash materials associated with the above work. Worker's Compensation and General Liability insurance is included on all portions of work performed.

Thank you for the opportunity to work with you on this project.

Respectfully,

John Jurkiewicz  
E-J Builders, Inc.

**Baldwin County Commission**

**Elberta, Alabama, East Fork Landfill Scale House Deck Project**

(2) 5ft x 5ft wood decks with stairs, handrails and covered awnings on back entrance of scale house

(1) 5ft x 48ft wood deck with handrails and 5ft wheel chair access with full length covered awnings on front of scale house

\*Treated 4x4 support posts used for framing support set in concrete

\*Treated 2x10 gurdur supports on 8ft centers

\*Treated 2x8 stringer supports on 16" centers

\*Composite boards used for decking

\*Treated 2x6 gurdur and rafter supports

\*Galvanized 26 metal for roof sheathing and trim

-All framing securement hardware will be galvanized (nails, bolts, screws etc.)

-Decks are required to be detached from scale house

-Ground work is needed between scales and scale house prior to construction for proper drainage. This will be done by DT Construction (Drainage design will need to be discussed with proper county official before construction)

-Elevation of decks are to be set at the bottom of threshold of the entrance doors

Design to follow drawn site construction plan provided

Any changes from plan will be considered a change order and could increase overall estimated price

Decks will be framed strong to withstand multiple public customer weight live loads

Project projected to take 3 weeks from initial start-up. (Due to high traffic area of incoming trucks and confined area between scale and scalehouse)

Any buried utility lines to be located prior to construction

Compensation draws to be discussed with proper county official before start date

**Grand total \$ 29,338.06**

David Tillery Jr - (251)591-5163 - [dtconstructionllc@hotmail.com](mailto:dtconstructionllc@hotmail.com) - 501 East 4<sup>th</sup> St Bay Minette AL 36507

825819

## Statement

DATE

10-2-20

TERMS

TO

BALDWIN County

East Fork Landfill

IN ACCOUNT WITH

Warriner Construction

13390 Norris Lane Foley, AL 36535

QUOTE FOR

Deck & ramps  
on Scalehouse  
at East Fork  
Landfill+ Awning  
Labor and  
Materials

29,500.00

CURRENT

OVER 30 DAYS

OVER 60 DAYS

TOTAL AMOUNT

\$29,500.00